


Annexure – L to Section – VII(B)
220 kV Transmission Line Right of Way

CTU has allotted 220 kV bays at Pavagada ISTS substation in the following order:



220kV Bay Allocation	
Bay No	Developer
218	Project Ten Renewable Power Pvt Ltd
221	SECI for 200MW RE GEN.
222	IRCON Renewable Power Ltd.
223	IRCON Renewable Power Ltd.

As per CTU’s connectivity procedure of clause 6 “Considering *Right-of-Way near substation for termination of number of 400/ 220kV dedicated transmission lines, the connectivity grantees may coordinate among themselves for implementation of 400/ 220kV lines (as applicable) through multi circuit tower near the substation entry for about 2-3 kms stretches*”.

The execution of bay no. 218 is being carried out by Project Ten Renewable Power Private Limited (PTRPPL), a Special Purpose Vehicle of Ayana Renewable Power Private Limited (ARPPL). The execution of bay no. 222 and 223 is being carried out by IRCON Renewable Power Limited (IRPL), a Joint Venture between IRCON International Limited (IIL) and Ayana Renewable Power Private Limited (ARPPL). In order to implement 220 kV multi-circuit towers near the ISTS substation, SECI, in discussion with IRPL and ARPPL, proposes the following arrangement.

Multi-circuit towers for about 4 km (AP4 to AP15) and double-circuit tower at AP17 as shown in Figure 1 will be constructed by IRPL. Stringing of conductors and OPGW from double-circuit tower at AP17 to bay no. 221 shall be in the scope of BoS Contractor. Shutdown of other circuits of shared multi-circuit/double-circuit towers for stringing and/or hot line stringing at the shared multi-circuit/double-circuit towers shall also be the responsibility of the BoS Contractor. Construction of 220 kV double-circuit transmission line from Solar Plant Pooling Substation till AP4 including Right of Way shall be in the scope of BoS Contractor.




Figure 1: Tentative multi-circuit transmission line route

KMZ file of Figure 1 is attached in the following link.

https://drive.google.com/file/d/10d2UvmFhNiXVdxkpiXvdfL_UhYvi6Nn/view?usp=sharing

[g](#)

Tentative multi-circuit transmission tower schedule is shown in Figure 2.




Figure 2: Tentative multi-circuit transmission tower schedule